

		Description of Equipment / Service	TOTAL Estimated Qty
1		CAMERA, NVR, Monitor & Switch	
2	supply	Network Video Recorder-16 Channel	12
3	supply	8TB Surveillance HDD	24
4	labor	Installation/Fixing/Configuration of Network Video Recorder -16 Channel	12
5	supply	4MP Dome Camera with motorised Varifocal Lens	192
6	labor	Mounting/Installation of 4MP Dome Camera	192
7	supply	24-inch QHD Monitor with VESA Wall-Mount&HDMI Cable	12
8	supply	8-Port-Gigabit PoE Network Switch, 4x 1G uplink ports	24
9	labor	Installation of 8-Port-Gigabit PoE Switch	24
10		RACKS & Accessories	
11	supply	4U Wall Mount Rack, Steel, Powder Coated (with power strip, lock and key)	36
12	labor	Mounting/Installation of 4U Wall-Mount Rack	36
13		UTP Cables, Connectors, Panels & Accessories	
14	supply	UTP Cable, Cat-6 4-Pair 23-AWG Gigabit (Box of 305 meters)	33
15	supply	Camera PVC Box	200
16	supply	RJ-45 Connector, Cat-6 Gigabit (Box of 100)	4
17	labor	Laying of UTP Cable, Indoor, in Conduit/Pipe/Duct	9900
18	labor	Installation/Fixing of Camera PVC Box	200
19	labor	Termination of RJ45 Connector Cable with Label	400
20		Piping, Laying	
21	supply	25mm/1" PVC Electrical Grade Conduit/Pipe. (Mfr Labeled, ISI Approved, White)	5000
22	supply	32mm/1.25" PVC Electrical Grade Conduit/Pipe. (Mfr Labeled, ISI Approved, White)	3000
23	supply	40mm/1.5" PVC Electrical Grade Conduit/Pipe. (Mfr Labeled, ISI Approved)	500
24	labor	Laying / fixing of PVC Conduit/Pipe	8500
25		Testing, Commissioning & Documentation	
26	labor	Signal Test-reports of each UTP node/link completed, complying to standards/specifications, alongwith Work-Completion Report	192