

27.Replacement of existing and Installation of new BACS.		
Sl. No	Item Description	Item Specification
1.	Replacement of existing BACS	All readers along with turnstile to be replaced with new one.
2.	Biometric Reader installation	Installation configuring and commissioning to be done for all readers which will be procured.
3.	Implementation charge of the system Software	Implementation of system software includes installation of software, commissioning and also basic training of the software to be given to LEOS personnel.
4.	Electromagnetic Lock installation	Installation, Configuration & Commissioning of Electromagnetic Lock
5.	Exit Switch installation	Installation, Configuration & Commissioning of Exit Switch
6.	Break Glass installation	Installation, Commissioning & Configuration of Break Glass
7.	Cable Laying and conduit laying	Cable Laying conduit laying charges also included in the installation charges
8.	Photo popup Unit installation	Installation, Configuration & Commissioning of Photo popup Unit
9.	Project Management Services	Project Management Services also included in the installation
10.	3 module switch box	Installation & Commissioning of 3 module switch box
11.	Swing gate barrier installation	Installation should also include civil work